

Annex B Price Form Breakdown

Field
Works

ITEM	DESCRIPTION	UNIT	RATE	QUANTITY	SUM
1	Mobilization	Lump Sum		1	
2	Traffic Control	Lump Sum		1	
3	Installation of BLDC Furnished - 4-inch PVC Communication Conduit	LF		1,923	
4	Installation of BLDC Furnished - 4-inch HDPE Pipe for Sanitary Sewer- Green Stripe	LF		1,075	
5	Installation of BLDC Furnished - 2-inch HDPE Pipe for Reclaimed Water- Lilac Stripe	LF		30	
6	Installation of BLDC Furnished - 4-inch HDPE Pipe for Reclaimed Water- Lilac Stripe	LF		982	
7	Installation of BLDC Furnished - 6-inch HDPE Pipe for Reclaimed Water- Lilac Stripe	LF		818	
8	Installation of BLDC Furnished - 8-inch HDPE Pipe for Potable Water- Blue Stripe	LF		1,048	
9	Supply of Fittings (Itemized Bill of Materials Sheet)	Lump Sum		1	
10	Excavation for Trench Type B	LF		875	
11	Excavation for Trench Type D	LF		982	
12	Excavation for Trench Type L	LF		66	
13	Installation of Trench Type B – Includes all pipe fittings, utility identification tape, subbase, backfill, embedment and connection	LF		875	

ITEM	DESCRIPTION	UNIT	RATE	QUANTITY	SUM
14	Installation of Trench Type D – Includes all pipe fittings, utility identification tape, subbase, backfill, embedment and compaction	LF		982	
15	Installation of Trench Type L – Includes all pipe fittings, utility identification tape, subbase, backfill, embedment and compaction	LF		66	
16	Clearing, Grubbing, Grading and Landscaping - includes topsoil, seeding and maintenance	SF		640	
17	Installation of BLDC Furnished Combination Air Release Valves - Sanitary Sewer	Unit Rate per Valve		3	
18	Installation of Concrete Block Manhole – Sanitary Sewer – Includes excavation, installation of block manhole, concrete base, manhole frame and cover, installation of interior piping, valves and accessories, and final grading	Unit Rate per Manhole		3	
19	Installation of BLDC Furnished Combination Air Release Valves - Reclaimed Water	Unit Rate per Valve		1	
20	Installation of Concrete Block Manhole – Reclaimed Water – Includes excavation, installation of block manhole, concrete base, manhole frame and cover, installation of interior piping, valves and accessories, and final grading	Unit Rate per Manhole		1	
21	Installation of BLDC Furnished Combination Air Release Valves - Potable Water	Unit Rate per Valve		1	
22	Installation of Concrete Block Manhole – Potable Water – Includes excavation, installation of block manhole, concrete base, manhole frame and cover, installation of interior piping, valves and accessories, and final grading	Unit Rate per Manhole		1	
23	Installation of BLDC Furnished 2-inch Gate Valve and Valve Box - Reclaimed Water	Unit Rate per Valve		1	
24	Installation of BLDC Furnished 4-inch Gate Valve and Valve Box - Reclaimed Water	Unit Rate per Valve		1	
25	Installation of BLDC Furnished 4-inch Gate Valve and Valve Box - Sanitary Sewer FM	Unit Rate per Valve		1	
26	Installation of BLDC Furnished 8-inch Gate Valve and Valve Box - Potable Water	Unit Rate per Valve		3	

ITEM	DESCRIPTION	UNIT	RATE	QUANTITY	SUM
27	Installation of Contractor provided Communications Handhole	Unit Rate per		5	
28	Installation of Contractor provided 4-inch HDPE to PVC Transition Coupling	Unit Rate per		1	
29	Installation of Contractor provided 6-inch HDPE to PVC Transition Coupling	Unit Rate per		1	
30	HDPE Pipe Connection New To Existing (Final & Temporary)	Unit Rate per		8	
31	PVC Pipe Connection New To Existing (Final & Temporary)	Unit Rate per		3	
32	Installation of BLDC Furnished 8-inch Electrofusion Tapping Sleeve and 6-inch Gate	Unit Rate per Tapping		1	
33	Installation of Contractor provided PVC Tapping Saddle	Unit Rate per Tapping		2	
34	Connection to RO Plant	Lump Sum		1	
35	Hydrostatic Testing (all piping)	Lump Sum		1	
36	Contractor specified items: Any elements of work or expenditure not covered elsewhere in the Tender Price Analysis and are necessary in the execution of this work. Proponent to itemize.	Lump Sum		1	
	TOTAL TENDER SUM FOR WATERMAIN WORKS	Sub Total		Sub Total	

Number of sheets, appended by the Proponent to this Form

_____ (if nil, enter NIL)

SIGNED ON BEHALF OF PROPONENT:

.....

ITEM	DESCRIPTION	UNIT	RATE	QUANTITY	SUM
------	-------------	------	------	----------	-----

Labour & Equipment Rates for Works

Labour and Mark-Up Rates

ITEM	DESCRIPTION	QUANTITY	RATE
1	Foreman/Site Supervisor	Hourly Rate	
2	Pipe Fitter	Hourly Rate	
3	Labour	Hourly Rate	
4	Excavator/Trenching Machine (as required by contractor)	Hourly Rate	
5	Excavation of Hard Rock (contractor to state machine Size)	Hourly Rate	
6	Traffic Control	Hourly Rate	
7	Road Reinstatement and Sidewalk Repair	Hourly Rate	
8	Trucking	Hourly Rate	
9	Landscaping	Hourly Rate	
10	Contractor specified items: Additional Day Work Rates for Labour, Materials or Equipment necessary for the execution of this work. See		

Mark-Up Rates for WATER MAIN Works

ITEM	DESCRIPTION	RATE (%)
1	Overhead and Mark-Up (own work)	
2	Mark-Up (Sub-Contracted labour and materials)	

Signed _____
 (1) _____ Title _____ Date _____
 for and on behalf of _____